| | | | | | | |
|---|---|---|---|---|---|---|
| | | | | | | |
| | | **Town of Vernon Fire Department** | | | | |
| | | **Pumper Radio Equipment** | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | **Item #** | **Description** | **Detailed Description** | **QTY** | **Each** | **Amount** |
| | | | | | | |
| | **Setcom Head Set System ( Wired Configuration)** | | | | | |
| | IM-900E | Master Station System 900E | Radio Interface, Full Duplex | 1 | | |
| | CSB-900R | Headset (Right Exit) | Radio Transmit Dual Ear Muff, Behind the head, 15' coiled cord | 2 | | |
| | CSB-900L | Headset (Left Exit) | Radio Transmit Dual Ear Muff, Behind the head, 15' coiled cord | 1 | | |
| | PS-90040 | Pump Panel | 40' Cable with Weatherproof Enclosure | 1 | | |
| | JS-901-20 | Jumpseat Station | 2 jacks intercom only with extension port 20' cable | 1 | | |
| | JS-900 | Jumpseat Station | 2 jacks intercom only 15' cable | 1 | | |
| | CSB-901R | Headset (Right Exit) | Intercom only for jump seat, 15' coiled cord | 2 | | |
| | CSB-901L | Headset (Left Exit) | Intercom only for jump seat, 15' coiled cord | 2 | | |
| | 9RC-6IKO | Radio Cable | control head, for dual radio heads. | 2 | | |
| | RSM-902 | Radio Select Modual | Dual radios with same mic levels | 1 | | |
| | | | | | | |
| | | | | | | |
| | **Radio System for Pumpers** | | | | | |
| | **Item #** | **Description** | **Detailed Description** | **QTY** | **Each** | **Amount** |
| | **LOW Band Mobile RADIO** | | | | | |
| | TK-690HBK | Kenwood Radio Chassis | 100Watt low band chassis | 1 | | |
| | 9FHSH1 | Kenwwod Radio Control Head | Full Featured Remote Control Head | 1 | | |
| | L846 | Assembly Costs | Single band singe head assembly cost | 1 | | |
| | KLF 2 | Kenwood Noise Filter | Filter for low band radio | 1 | | |
| | Misc | Shure Microphone | Microphone for pump panel operation | 1 | | |
| | Cable | Remote control cable | 50' remote cable to pump panel for mic & speaker | 50 | | |
| | KES-5 | Kenwood Remote Speaker | Remote Pump Panel Speaker | 1 | | |
| | Labor | Installation Labor | Radio only Installation Estimate | 16 | | |
| | MNO 30 | Larson Antenna | Larson low band antenna | 1 | | |
| | K794 | Antennex cable & mount | 3/8 Thick Mount with RG58/U Antenna Cable. (1) spare mount | 2 | | |
| | PL 259 | Antenna Connector | Antenna Connector for low band radio | 1 | | |
| | | | | | | |
| | | | | | | |
| | **UHF Mobile RADIO** | | | | | |
| | TK-890 BK | Kenwood UHF Chassis | 40 Watt UHF radio chassis | 1 | | |

| | | | | | |
|---|---|---|---|---|---|
| | **Town of Vernon Fire Department** | | | | |
| | **Pumper Radio Equipment** | | | | |
| **Item #** | **Description** | **Detailed Description** | **QTY** | **Each** | **Amount** |
| 9FMSH-1 | Kenwood Radio Control Head | Full Featured Remote Control Head | 1 | | |
| L-846 | Assembly Cost | Single band singe head assembly cost | 1 | | |
| Misc | Shure Microphone | Microphone for pump panel operation | 1 | | |
| Cable | Remote control cable | 50' remote cable to pump panel for mic & speaker | 50 | | |
| KES-5 | Kenwood Remote Speaker | Remote Pump Panel Speaker | 1 | | |
| A/S 7795 | Maxrad | UHF Antenna | 1 | | |
| K794 | Antennex cable & mount | 3/8 Thick Mount with RG58/U Antenna Cable. (1) spare mount | 2 | | |
| Labor | Installation Labor included in Low Band Estimate | | | | |
| | | **Includes Headset, 2 Mobile Radios** | | | |
| **Options** | | | | | |
| 9FMDH1 | Kenwood Dual Head Option | May be required depending on Apparatus Cab Layout | 1 | | |
| | Setcom Wireless Option | | | | |
| CSB-900R | Delete wired headsets | | 1 | | |
| CSB-900L | Delete wired headsets | | 1 | | |
| 25-0730 | Setcom Adapter Cable | Wireless Adapter Cable | 2 | | |
| CSB-900W Kit | Setcom Wireless System | Wireless Headsets with Charging Base | 2 | | |