

ADDENDUM #1

CONTRACT #1099-10/06/2016

**FOR FURNISHING SEWER LINE CAMERA EQUIPMENT FOR THE TOWN
OF VERNON WATER POLLUTION CONTROL AUTHORITY**

“ATTACHMENT B”

1. Ford Transit T-250 build out to include:
 - a. Operator Studio to include:
 - i. Solid bulkhead wall with smoked window.
 - ii. Formica desk with wall outlets above and below.
 - iii. Built-in 2 drawer file cabinet with butcher block top.
 - iv. Overhead LED lighting.
 - v. Pass-through door with kick plate.
 - vi. Tru-Vu monitor.
 - vii. Operator chair.
 - viii. Carpeted walls and ceiling.
 - ix. Black treaded rubber floor.
 - x. Safety light switches in truck cab.
 - xi. Rack cabinet for computer.
 - xii. Wall file.
 - xiii. Video Distribution booster.
 - xiv. 13,500 BTU roof air conditioner with 5,600 BTU heat strip.

b. Equipment bay to include:

- i. Butcher block work surfaces.
- ii. Built-in heavy duty storage/tool chest.
- iii. Slide-out crawler tray under cable reel.
- iv. Wash down system which includes
 - a. On-demand pump.
 - b. Lighted switch
 - c. 10-gallon water tank with exterior fill.
 - d. 25 foot retractable hose reel.
- v. Ceiling mounted LED lights.
- vi. Rear-facing Tru-Vu monitor.
- vii. Grey FRP over plywood walls and ceiling.
- viii. Black treaded rubber floor.
- ix. Aluminum storage shelf and caddy.
- x. Wheel drawer.
- xi. Rubber glove dispenser.
- xii. Tool mounts and brackets to include:
 - a. Manhole hook.
 - b. Pick.
 - c. Shovel.

c. Power Options to include:

- i. 6.3 kW MEPS Roadpower source.

- ii. Shore power cord.
 - iii. Breaker box.
 - iv. Auto-transfer switch.
 - v. 12V fuse block.
- d. Exterior to include:
- i. Tie-off clamp above rear bumper.
 - ii. Corner mounted LED spotlights.
 - iii. Front roof mounted LED strobe lights.
 - iv. Rear LED arrow board.
 - v. Backup alarm.