

Vernon Center Middle School
Partial Roof Replacement
777 Hartford Turnpike, Vernon CT

Maier Design Group Project No. 2018.018
State Project No. SDE-146-0139

Date: 18 May 2018

Addendum #2

Part 1 – General:

1. This Addendum is to modify the Contract Documents dated 2 May 2018. The provisions of this Addendum shall become part of the Contract Documents and all work shall conform to those standards.
2. The selected Contractor shall be responsible for notifying all subcontractors and material suppliers of the contents and requirements of this Addendum. Except as modified, all provisions of the Contract Documents shall remain in force.
3. A link to electronic drawings are available to contractors who have purchased a set of physical plans and specifications from the Town. The link can be requested from Robert Kleinhans via email at rkleinhans@vernon-ct.gov

Part 2 – Clarifications:

1. All existing single body roof drains are to be replaced with dual body roof drains with overflow piping as specified on the documents. Overflow piping locations shown on the drawings are schematic in nature. The successful bidder's plumbing contractor to coordinate the actual overflow piping runs with the Architect and the School's facilities director.
2. Approximately 18 of the original drains are 5" bowls with 5" piping. All new replacement drains, including the 18 mentioned above, shall be replaced with 4" dual body drains that are tied into the existing 5" drainage piping. New overflow piping for the drains shall be 4" as specified.

END OF ADDENDUM #2