

Contract #941-11/23/09 Talcottville Improvements Questions and Answers.

- Q. What is the post connection detail for the proposed kiosk?
- A. Post diameter remains 12” as per plan. The countersink depth for the fasteners connecting the post to the foundation is ½”. The detail originally showed a different dimension. See attached detail.
- Q. The description of plants on L-101 do not match the plant sizes on the bid form (G-003)?
- A. The plant list on Sheet L-101 is correct.
- Q. Is Contract Time and Liquidated Damages 180 days or 90?
- A. Ninety (90) calendar days will be allowed for completion of the work on this Project and the liquidated damages charge to apply will be **Five Hundred Dollars** (\$500) Hundred Dollars (\$500) per calendar day.
- Q. Please verify the quantity of “Information Sign”. The unit calls for 14, however the drawings shows 15.
- A. This the correct quantity for this item and includes the area beneath the kiosk.
- Q. Verify quantity of “Precast Concrete Paver Sidewalk?”
The unit calls for 490 S.F. Do the pavers cover the entire area beneath the kiosk? If not, what material is beneath the kiosk?
- A. This is the correct quantity for this item and includes the area beneath the kiosk.
- Q. Please provide specification for Item 0612994 “Concrete cylinder curing box.
- A. This item shall be subject to the requirements of Section 6.12 of ConnDOT standard specifications Form 816.